

August 29, 1995

Mr. Richard Spiese State of Vermont Department of Environmental Conservation Hazardous Materials Management Division 103 South Main Street / West Office Building Waterbury, VT 05671-0404

RE: Summary Report on the Investigation of Petroleum Contamination at Chipman Point

Marina, Orwell, Vermont (VTDEC Site #94-1739)

Dear Mr. Spiese:

Enclosed please find the summary report on the investigation of petroleum contamination at the Chipman Point Marina in Orwell, Vermont.

If you have any questions regarding our findings, please call.

Sincerely,

Kevin McGraw Hydrogeologist

enclosure

SUMMARY REPORT ON THE INVESTIGATION OF PETROLEUM CONTAMINATION

\mathbf{AT}

CHIPMAN POINT MARINA ORWELL, VERMONT

AUGUST 1995

Prepared by:



P.O. Box 943 Williston, Vermont 05495 (802) 865-4288

TABLE OF CONTENTS

		PAGE
I.	INTRODUCTION	1
II.	SITE BACKGROUND	1
III.	SITE INVESTIGATION A. Lake Sediment Sampling B. Supply Well Sampling	1
IV.	ANALYTICAL RESULTS A. Lake Sediment B. Supply Well	2
V.	SENSITIVE RECEPTOR ASSESSMENT	3
VI.	STOCKPILED SOIL SCREENING	4
VII.	CONCLUSIONS	4
VIII.	RECOMMENDATIONS	5
	APPENDICES	
APPE	Site Location Map Site Map Area Map	
APPE	NDIX R. Laboratory Reports	

I. INTRODUCTION

The following report summarizes the limited investigation of subsurface petroleum contamination conducted at the Chipman Point Marina in Orwell, Vermont (see Site Location Map, Appendix A). This investigation is a follow-on action to the discovery of petroleum-contaminated soils at the site during the removal of underground storage tanks (USTs) in December of 1994. Griffin International, Inc. (Griffin) has conducted this investigation for Mr. Richard Ullom, owner of the Chipman Point Marina. The assessment has been conducted in accordance with Griffin's approved work plan and cost estimate, dated January 16, 1995.

II. SITE BACKGROUND

On December 19, 1994, two (2) 1,000-gallon gasoline USTs and one (1) 1,000-gallon diesel UST were removed from the subsurface at the Chipman Point Marina. These tanks were located on the west side of the marina building, within 5 feet of Lake Champlain (see Site Map, Appendix A). The tanks were partially below the lake level, which was seasonally low, at the time of removal. In the spring, the lake level rises sufficiently to flood the area where the tanks were located. As a result, the seasonal rise and fall of the lake flushes the area around the tanks at least once each year.

The diesel tank, reportedly 10 to 12 years old upon removal, was observed to be in good condition. One of the gasoline tanks, approximately 30 years old, was found to be in poor condition; five (5) 1/4-inch diameter holes were discovered on this tank. The second gasoline tank was in fair condition. Gasoline-contaminated soils were observed beneath both former gasoline tanks. No diesel contamination was observed during the removal of the tanks. Approximately 10 cubic yards of contaminated soils were stockpiled on-site prior to the installation of one 2,000-gallon gasoline UST. On the day the USTs were removed, the Lake Champlain shoreline in the vicinity of the marina was surveyed for signs of petroleum contamination. No sheens, odors or seeps were observed at the edge of the lake.

In response to the subsurface petroleum contamination discovered during the removal of the USTs, the Vermont Department of Environmental Conservation (VTDEC) requested additional investigation at this site to determine the potential for contaminant impact to the lake and other receptors. The following report presents the results of the investigation proposed by Griffin in the work plan and cost estimate submitted to the VTDEC on January 16, 1995.

III. SITE INVESTIGATION

A. Lake Sediment Sampling

The two former gasoline underground storage tanks that are suspected of leaking were located at the immediate edge of Lake Champlain behind a concrete retaining wall. To determine if the lake has been impacted by the contamination on the east side of the retaining wall, five lake

sediment samples were collected along the west side of the wall. A hand auger could not be used to collect these samples due to the presence of primarily gravel and cobbles at the edge of the lake. Instead, grab samples were collected by hand in the five locations marked on the Site Map. Each of these sediment samples were screened for volatile organic compounds (VOCs) using a photoionization device (PID). The screening results for these samples were:

Sample #1: 0.0 parts per million (ppm)

Sample #2: 0.0 ppm Sample #3: 0.0 ppm Sample #4: 2.4 ppm Sample #5: 12 ppm

All of these samples consisted of coarse sand and gravel. Petroleum odors were not detected in samples #1, #2 or #3. Slight weathered petroleum odors were observed in samples #4 and #5, obtained from the west side of the retaining wall closest to the former gasoline tanks. A lake sediment sample was also collected for laboratory analysis from the vicinity of where sample #5 was obtained. This lab sample was analyzed for Total Petroleum Hydrocarbons (TPH) by Modified EPA Method 8100 and specific petroleum compounds by EPA Method 8020.

B. Supply Well Sampling

The closest known sensitive receptor, other than Lake Champlain, is the Chipman Point Marina supply well. A water sample was collected from this well on June 20, 1995. The sample was submitted to a laboratory and analyzed for TPH by Modified EPA Method 8100 and petroleum compounds by EPA Method 8020.

IV. ANALYTICAL RESULTS

A. Lake Sediment

The concentration of total petroleum hydrocarbons in the Lake Champlain sediment sample (sample #5) was 15.6 ppm. Very low concentrations of benzene, toluene, ethylbenzene, xylenes (BTEX) and methyl tert butyl ether (MTBE) were detected in this sample also. Benzene was detected at a concentration of 21.4 parts per billion (ppb). MTBE, a gasoline additive, was detected at a concentration of 56.4 ppb. All laboratory analytical results for the lake sediment sample are presented in Appendix B.

According to the Vermont Hazardous Waste Management Regulations (Section 7-207), wastes are considered hazardous by the characteristic of toxicity if the waste contains contaminants at or above EPA Maximum Contaminant Concentrations. These characteristics are based on the Toxicity Characteristic Leaching Procedure (TCLP). The 8020 analysis performed on the lake sediment sample is a direct method of analysis, which means the reported concentrations of the individual compounds (e.g., BTEX and MTBE) reflects the concentrations of these compounds in the sediment, while the TCLP would report the concentration extracted into a buffer solution.

Benzene was the only compound analyzed for that has a maximum concentration listed for the characteristic of toxicity (0.5 mg/Liter). To determine the (maximum) concentration of benzene which would have resulted from a TCLP analysis, a conversion must be performed. The proper conversion factor to obtain results comparable to a TCLP analysis was provided by Harry Locker, Ph.D., the laboratory director at Endyne Laboratories in Williston, Vermont.

Given that the concentration of benzene in the sediment sample, as determined by the direct method, was 21.4 ug/kg (ppb), the concentration as determined by the TCLP analysis would have likely been no greater than 1.07 ug/L or 0.00107 mg/L. This value is far less than the maximum concentration of 0.5 mg/L (shown in Table 1 of Section 7-207 of the Vermont Hazardous Waste Management Regulations).

The above analysis, although not conclusive, is a strong indication that the sediments sampled at Chipman Point Marina would not likely be considered hazardous waste by the characteristic of toxicity. In addition, the low concentrations of BTEX and MTBE observed in the sediments immediately outside the concrete retaining wall will not likely result in any significant concentrations of these compounds in the lake water itself. Contaminants entering the lake from the vicinity of the former gasoline USTs will likely be diluted to non-detectable levels in the general area of the marina.

B. Supply Well

Dissolved petroleum contamination was not detected in the water sample collected from the Chipman Point Marina supply well by Modified EPA Method 8100 or Method 8020. The laboratory analytical report is included in Appendix B.

V. SENSITIVE RECEPTOR ASSESSMENT

On June 20, 1995, Griffin surveyed the area to identify the location of potential sensitive receptors in the area. The only potential receptors identified were Lake Champlain and the Chipman Point Marina supply well.

The supply well for the marina is located approximately 500 feet east of the former gasoline tanks at the lake's edge (see Area Map, Appendix A). The risk to this supply well is deemed to be minimal at this time. It is highly unlikely that dissolved petroleum contamination from the former or present marina USTs would ever impact this well.

Lake Champlain has likely been impacted to a minimal degree from the gasoline release at this site. Sediment sampling and screening results suggest that only a narrow strip of shoreline has been impacted by the petroleum release. As stated previously, any dissolved contamination in the lake resulting from the gasoline release will likely be reduced to non-detect levels in the vicinity of the marina.

Based on the location of nearby buildings relative to the subsurface contamination, it is does not appear that there are any basements in the area that are at risk of petroleum vapor accumulation.

VI. STOCKPILED SOIL SCREENING

On December 19, 1994, approximately 10 cubic yards of petroleum-contaminated soils were stockpiled on-site during the removal of the three former USTs. The soils are currently on plastic sheeting and are covered with plastic sheeting to prevent leaching of contaminants into the surrounding soils. On June 20, 1995, Griffin screened the stockpiled soils for VOCs using a PID. Ten random samples were collected from the center of the soil pile, placed in Ziploc baggies and then screened for VOCs. No VOCs were detected in any of the ten soil samples; all PID readings were 0.0 or 0.2 ppm. The background PID reading at the time of screening was 0.2 ppm. Based on these soil screening results, Griffin recommends that the soils be spread on-site.

VII. CONCLUSIONS

Based on the limited site investigation conducted at the Chipman Point Marina, Griffin has reached the following conclusions:


- 1. There has been a release of gasoline to the subsurface at Chipman Point Marina which has resulted in adsorbed and dissolved-phase contamination. This contamination likely exists primarily below the water table in the vicinity of the former USTs and at the bottom of the lake. A significant portion of the soil contamination above the water table was removed during excavation of approximately 10 cubic yards of contaminated soil.
- 2. The low concentrations of BTEX, MTBE and TPH in the lake sediment sample do not likely pose a significant threat to the lake ecosystem. Any petroleum contamination leaching into the lake in the vicinity of the former gasoline USTs is likely reduced to non-detectable levels by dilution. Analysis of lake water directly above these sediments has not been conducted.
- 3. The concentration of residual petroleum contamination in the soils will reduce naturally over time by the processes of biodegradation and the "flushing action" of rising and falling lake levels.
- 4. The only apparent effective method of remediation of petroleum contamination in the vicinity of the former USTs is excavation of a portion of the shoreline and dredging of the lake bottom. This option is impractical, however, as shoreline alterations and lake bottom dredging would require significant efforts related to obtaining both state and federal approval. In addition, the level of contamination which exists at this site does not appear to warrant these efforts.
- 5. The risk to the Chipman Point Marina supply well is likely minimal. It is highly unlikely that this well, located approximately 500 feet physically upgradient from the source area, would ever be impacted by the release of gasoline from the former gasoline USTs.
- 6. Residual petroleum contamination in the stockpiled contaminated soils has been reduced to non-detectable levels since December of 1994.

VIII. RECOMMENDATIONS

Based on the above conclusions, Griffin does not recommend any additional investigation at this site. The stockpiled soils should be spread on-site since no contamination was detected during the screening conducted in June.


APPENDIX A - MAPS

Site Location Map Site Map Area Map




SITE LOCATION MAP
Chipman Point Marina, Orwell, Vermont

SOURCE: U.S.G.S. - TICONDEROGA, VT-NY (1950), SCALE 1:62,500



SITE MAP

Chipman Point Marina
Orwell, Vermont
Scale: 1" = 10'



AREA MAP

Chipman Point Marina Orwell, Vermont Not to Scale

APPENDIX B

Laboratory Reports



32 James Brown Drive Williston, Vermont 05495 (802) 879-4333 FAX 879-7103

REPORT OF LABORATORY ANALYSIS

CLIENT: Griffin International

PROJECT NAME: Chipman Point Marina

DATE REPORTED: July 11, 1995 DATE SAMPLED: June 20, 1995 PROJECT CODE: GICP1372

REF. #: 75,937 - 75,938

Enclosed please find the results of the analyses performed for the samples referenced on the attached chain of custody record.

Chain of custody indicated water sample preservation with HCl.

All samples were prepared and analyzed by requirements outlined in the referenced methods and within the specified holding times.

All instrumentation was calibrated with the appropriate frequency and verified by the requirements outlined in the referenced methods.

Blank contamination was not observed at levels affecting the analytical results.

Analytical method precision and accuracy were monitored by laboratory control standards which included matrix spike, duplicate and quality control analyses. These standards were determined to be within established laboratory method acceptance limits.

Reviewed by,

Harry B. Locker, Ph.D. Laboratory Director

enclosures



32 James Brown Drive Williston, Vermont 05495 (802) 879-4333 FAX 879-7103

Concentration

LABORATORY REPORT

TOTAL PETROLEUM HYDROCARBONS (TPH) BY MODIFIED EPA METHOD 8100

DATE: July 11, 1995

CLIENT: Griffin International PROJECT: Chipman Point Marina PROJECT CODE: GICP1372 COLLECTED BY: Kevin McGraw DATE SAMPLED: June 20, 1995 DATE RECEIVED: June 21, 1995

Reference #	Sample ID	(mg/kg as received)1
75,937	Supply Well; 11:30	ND^2
75,938	Sediment Sample #1; 1:45	15.6

Notes:

- 1 Method detection limit is 5.0 mg/kg.
- 2 None Detected. Detection limit for sample 75,937 is 1 mg/L.

CHAIN-OF-CUSTODY RECORD Job# 2954645 14575

Project Name: Chipman Point Maring Site Location: Orwell, VT							Reporting Address: Griffin International								Billing Address: Griffin International				
Endyne Project Number:						Company: Griffin International Contact Name/Phone #: Kevin McGraw /865-4288								Sa Ph	Sampley Manage K. A.C.C.				-
	2b#	Sa	mple Lo	cation	Mati	ix	G R A B	C M P	Date/Ti 6/20	me	Samp No.	ole Containers		Fleid)	Results/Remarks		Analysis Required	Sample Preservation	Rush
_		Jupply	<u> Jell</u>		H2	0	V		11:3	, , , ,	2	40mL	100000000000000000000000000000000000000			- -	20-2-2	410.	
75,	937	Supply	<u>Well</u>		H2	0	/		11:3	0	2	1,000 mL					2020	HCI	
ļ <u>.</u>		, , , , , , , , , , , , , , , , , , ,										1				_ 158	20	HCI	<u> </u>
77.0		Sediment	<u>Sau</u>	1ple#)	Soi		7		1:4	5	2	250-4	<u> </u>			- Q	0 2 0	 	
1/5,	<u>938</u>	Sediment	Sam	ple#1	Soi		1		1:4:		2	2-50 m L					0 20	<u> </u>	
					<u>.</u>	\perp										623	567 67.03		
						Т						 	·			- -		 	
						\top			<u>-</u>			 							
<u>.</u>	<u></u>											 	· · · · · · · · · · · · · · · · · · ·						
						T	_				_	 -				_ _	· · · ·		
					· · · · ·										<u> </u>				
						_ -										_			
Relina	nished by	: Signature	- 0	110 1			=			===						<u> </u>			
7.02.11	uisnea o,	: Signature The	~ 1/1	115than		Recei	ved by	: Signate	ire Sc	th	W	ard		Date	Time 6 - 21—	95	9.	40	
Reling	uished by	: Signature,	10	(1)-1		Dan:												<i>TO</i>	
-			th	Ward		NCCC1	ved by	: Signaid	ire Rose	and		Sesser	ار	Date/	Time Walle	-	Civ. 16		
		Project: Yes	No	<u> </u>		<u> </u>			Requeste	d Ana	ilyse		<u></u>	<u></u>	<u> </u>		7.95	A.M.	
2	pН		6	TKN		11	Tot	al Solids		16	I N	detais (Specify)		21	EPA 624	- 11-			
3	Chloric Ammo		7	Total P		12	TS:	3		17	7	Coliform (Specify)	, 	22	EPA 625 B/N or A	╼╌┼┼╌╌		4 8270 B/N or Acid	d
4	Nitrite		8	Total Diss. P		13	TD			18	C	OD		23	EPA 418.1	╾╌╢╌		A 8010/8020 A 8080 Pest/PCB	
5	Nitrate		10	BOD _s Alkalinity		14				19	BTEX		24	EPA 608 Pest/PCB	-#-		- JOSO PESUPCB		
29			lt	, metals, pesticides, he		15	Cor	ductivity		20	E	PA 601/602		25	EPA 8240				
(30)										<u> </u>									
			3700,00 2 64,	and cowast is also	3.0					 :									

32 James Brown Drive Williston, Vermont 05495 (802) 879-4333 FAX 879-7103

REPORT OF LABORATORY ANALYSIS

CLIENT: Griffin International

PROJECT NAME: Chipman Point Marina

DATE REPORTED: June 29, 1995 DATE SAMPLED: June 20, 1995 PROJECT CODE: GICP1372

REF. #: 75,935 - 75,936

Enclosed please find the results of the analyses performed for the samples referenced on the attached chain of custody record.

Chain of custody indicated the water sample was preserved with HCl.

All samples were prepared and analyzed by requirements outlined in the referenced methods and within the specified holding times.

All instrumentation was calibrated with the appropriate frequency and verified by the requirements outlined in the referenced methods.

Blank contamination was not observed at levels affecting the analytical results.

Analytical method precision and accuracy were monitored by laboratory control standards which included matrix spike, duplicate and quality control analyses. These standards were determined to be within established laboratory method acceptance limits.

Individual sample performance was monitored by the addition of surrogate analytes to each sample. All surrogate data was determined to be within Laboratory QA/QC guidelines unless otherwise noted.

Reviewed by,

Harry B. Locker, Ph.D. Laboratory Director

F RECEIVED JUL - 3 1995

enclosures



32 James Brown Drive Williston, Vermont 05495 (802) 879-4333 FAX 879-7103

LABORATORY REPORT

EPA METHOD 8020 COMPOUNDS BY EPA METHOD 8260

CLIENT: Griffin International

PROJECT NAME: Chipman Point Marina

REPORT DATE: June 29, 1995 SAMPLER: Kevin McGraw

DATE SAMPLED: June 20, 1995 DATE RECEIVED: June 21, 1995 PROJECT CODE: GICP1372 ANALYSIS DATE: June 27, 1995

STATION: Supply Well

REF.#: 75,935

TIME SAMPLED: 11:30

<u>Parameter</u>	Detection Limit (ug/L)	Concentration (ug/L)			
Benzene	1	ND ¹			
Chlorobenzene	2	ND			
1,2-Dichlorobenzene	2	ND			
1,3-Dichlorobenzene	2	ND			
1,4-Dichlorobenzene	2	ND			
Ethylbenzene	1	ND			
Toluene	2	ND			
Xylene	3	ND			
MTBE	3	ND			

NUMBER OF UNIDENTIFIED PEAKS FOUND: 0

ANALYTICAL SURROGATE RECOVERY:

Dibromofluoromethane:	108.%
Toluene-d8:	102.%
4-Bromofluorobenzene:	98.%

NOTES:

1 None detected

32 James Brown Drive Williston, Vermont 05495 (802) 879-4333 FAX 879-7103

LABORATORY REPORT

EPA METHOD 8020 COMPOUNDS BY EPA METHOD 8260

CLIENT: Griffin International

PROJECT NAME: Chipman Point Marina

REPORT DATE: June 29, 1995

SAMPLER: Kevin McGraw

DATE SAMPLED: June 20, 1995 DATE RECEIVED: June 21, 1995

PROJECT CODE: GICP1372 ANALYSIS DATE: June 27, 1995

STATION: Sediment Sample #1

REF.#: 75,936

TIME SAMPLED: 1:45

<u>Parameter</u>	Detection Limit (ug/kg)	Concentration As Received (ug/kg)
Benzene	10	21.4
Chlorobenzene	20	ND¹
1,2-Dichlorobenzene	20	ND
1,3-Dichlorobenzene	20	ND
1,4-Dichlorobenzene	20	ND
Ethylbenzene	10	25.6
Toluene	10	26.8
Total Xylenes	30	134.
MTBE	30	56.4

NUMBER OF UNIDENTIFIED PEAKS FOUND: 4

ANALYTICAL SURROGATE RECOVERY:

Dibromofluoromethane: 87.% 104.% Toluene-d8:

100.% 4-Bromofluorobenzene:

PERCENT SOLIDS: 80.%

NOTES:

1 None detected

ENDYNE, INC.

32 James Brown Drive Williston, Vermont 05495 (802) 879-4333

GICP 1372

CHAIN-OF-CUSTODY RECORD

Job#2954645

14575

Project Site Lo	Name: Chipman exation: Orwell	† Marina		Reporting Address: Griffin International							Billing Address: Griffin International				
Endyne Project Number:									iternatio Graw/865		Sampler Name: Kevin McGraw Phone #: 865 - 4288				
Lab #	y Sam	ple Loca	tion	Matrix	G R A B	C O M P	Date/Time	—	ople Containers Type/Size		Field Re	sults/Remarks	Analysi Require	M 98, 99 in 600 Section 1 100 100 M	Rush
759	35 Supply L	<u>Jell</u>		H20			11:30		2 40mL				802	HCI	
			H20	/	<u></u>	11:30	12	2 1,000 mL				502 30			
75,93				Soil	/		1:45		250mL				8 0 20		
	Sectionent Sample #1 Soi				1		1:45	2	250mL				also 3	9	
•														<u> </u>	
												,			
							•								
				<u> </u>	<u> </u>	}		<u> </u>							
Relinquis	shed by: Signature Xew	91	16than		Received by: Signature Beth Ward						Date/Time 6 - 21 - 95 9:40				
Relinquis	shed by: Signature	th	ulard		Received by: Signature Ryslem Bouler						Date/Time 6/21/9 9:1574.M.				
New York	State Project: Yes	No					Requested		yses			(***)			
1	рН	6	TKN		11 Total Solids		s	16	Metals (Specify)		21	EPA 624	26 EPA 8270 B/N or Aci		cid
2	Chloride				12 TSS			17	Coliform (Specify)		22	EPA 625 B/N or A	27	EPA 8010/8020	
3	Ammonia N			. #	13 TDS			18	COD		23	EPA 418.1	28	EPA 8080 Pest/PCI	3
5	Nitrate N	Nitrite N 9 BOD, Nitrate N 10 Alkalinity			14	Turbidity Conductivity		19	BTEX		24	EPA 608 Pest/PCB	 		
29	TCLP (Specify: volatiles, serr		Alkalinity metals, pesticides, by	erbicides)		Conductivi	·9	20	EPA 601/602	<u> </u>	25	EPA 8240		·	
(30)			dified 1TP	· · · · · ·	. `						 			<u></u>	
11.57	G 010	+ 10	arried 111	יון טועונ											<u></u>]